



BRICK SIDEWALK

NOTE:

1. MORTAR LEVELING BED WILL BE PLACED AFTER THE CONCRETE BASE HAS SET FOR SEVEN (7) DAYS.
2. SIDEWALKS TO BE BUILT IN COMPLIANCE WITH ADA REGULATIONS.



BRICK SIDEWALK SECTION

City of Lowell Standard Specifications and Details

Spec. Ref #: 243-61.A(3)

Date: 10/01/2025

Scale: N.T.S.